



AREA 3: WORK AREA REFLECTED CEILING PLAN

	E
	Ø162MM ALUMINUM HOUSING RECESSED, CLEAR DIFFUSER, 18W PHILIPS LED DOWNLIGHT, WARM WHITE E27, AT 3000K QUANTITY: 6PCS.
•••	1220MM (L) x 220MM (W), 60W, WALDMANN LUMINAIRE, ANODISED ALUMINUM HOUSING SUSPENDED, COOL WHITE, 4000K QUANTITY: 84PCS.
	1163.2MM (L) Ø17MM 25W PHILIPS LED, WARM WHITE E27, AT 3000K QUANTITY: 34PCS.
AUXILIARY FIX	FURES DESCRIPTION
SD	OPTICAL SMOKE DETECTOR QUANTITY: 8PCS.
€ _{SP}	OVERHEAD SPRINKLER QUANTITY: 28PCS.
ССТУ	DOME CCTV CAMERA QUANTITY: 2PC.
00	EMERGENCY LIGHT QUANTITY: 7PCS.
\bullet	ENERGENCY EXIT SIGN QUANTITY: 3PCS.
	IN-CEILING SPEAKER QUANTITY: 9PCS.
	1200MM (L) x 150MM (W) STAINLESS STEEL AIRCON VENT QUANTITY: 20PCS.
CEILING FINISHES	DESCRIPTION
CF-01 3500MM	22MM THK, ARMSTRONG FIBERGLASS ACOUSTIC TILES, MOUNTED 3500MM FROM FFL. QUANTITY: 395PCS.
CF-02 3500MM	30MM THK, SUSPENDED ARMSTRONG METAL BAFFLES IN MATTE ANODIZED FINISH, MOUNTED 3500MM FROM FFL.